# NATIONAL BUREAU OF STANDARDS REPORT

7152

INFILTRATION MEASUREMENTS IN TEN ELECTRICALLY HEATED HOUSES

by

Carl W. Coblentz
Paul R. Achenbach
and
Richard S. Gray

Report to

Rural Electrification Administration
U.S. Department of Agriculture
Washington 25, D. C.

<NBS>

## U. S. DEPARTMENT OF COMMERCE

## NATIONAL BUREAU OF STANDARDS

# THE NATIONAL BUREAU OF STANDARDS

## Functions and Activities

The functions of the National Bureau of Standards are set forth in the Act of Congress, March 3, 1901, as amended by Congress in Public Law 619, 1950. These include the development and maintenance of the national standards of measurement and the provision of means and methods for making measurements consistent with these standards; the determination of physical constants and properties of materials; the development of methods and instruments for testing materials, devices, and structures; advisory services to government agencies on scientific and technical problems; invention and development of devices to serve special needs of the Government; and the development of standard practices, codes, and specifications. The work includes basic and applied research, development, engineering, instrumentation, testing, evaluation, calibration services, and various consultation and information services. Research projects are also performed for other government agencies when the work relates to and supplements the basic program of the Bureau or when the Bureau's unique competence is required. The scope of activities is suggested by the listing of divisions and sections on the inside of the back cover.

## Publications

The results of the Bureau's work take the form of either actual equipment and devices or published papers. These papers appear either in the Bureau's own series of publications or in the journals of professional and scientific societies. The Bureau itself publishes three periodicals available from the Government Printing Office: The Journal of Research, published in four separate sections, presents complete scientific and technical papers; the Technical News Bulletin presents summary and preliminary reports on work in progress; and Basic Radio Propagation Predictions provides data for determining the best frequencies to use for radio communications throughout the world. There are also five series of nonperiodical publications: Monographs, Applied Mathematics Series, Handbooks, Miscellaneous Publications, and Technical Notes.

Information on the Bureau's publications can be found in NBS Circular 460, Publications of the National Bureau of Standards ($1.25) and its Supplement ($1.50), available from the Superintendent of Documents, Government Printing Office, Washington 25, D.C.

# NATIONAL BUREAU OF STANDARDS REPORT

**NBS PROJECT**

**NBS REPORT**

1003-30-10630          May 18, 1961          7152

INFILTRATION MEASUREMENTS IN TEN ELECTRICALLY HEATED HOUSES

by

Carl W. Coblentz, Paul R. Achenbach
and Richard S. Gray
Mechanical Systems Section
Building Research Division

to
Rural Electrification Administration
U.S. Department of Agriculture
Washington 25, D. C.

IMPORTANT NOTICE

# U. S. DEPARTMENT OF COMMERCE

# NATIONAL BUREAU OF STANDARDS

# FOR OFFICIAL USE ONLY

# INFILTRATION MEASUREMENTS IN TEN ELECTRICALLY HEATED HOUSES

Carl W. Coblentz, Paul R. Achenbach
and Richard S. Gray

## 1. INTRODUCTION

The National Bureau of Standards, in cooperation with
the Rural Electrification Administration, made a field study
of the air infiltration in ten electrically heated houses
in the region of the Indiana Statewide Rural Electric Co-
operative, Inc., to obtain information that could be used to
better evaluate the heating load of similar houses. All
houses were occupied at the time of the tests, which caused
certain inconveniences to the occupants as well as to the
investigating team, and also affected, somewhat, the control
that could be maintained over the test conditions. Se-
lection of about a dozen houses had been planned for the
study of air infiltration, comprising various combinations
of one- and two-story brick and frame construction built
over basements, crawl spaces, or on concrete slabs-on-grade.
Not all of these twelve different constructions were availa-
ble for investigation in the Indiana Statewide Rural Electric
Cooperative region, so ten residences which comprised a good
variety of the desired features were selected.

## 2. DESCRIPTION OF HOUSES

The size, shape, and type of each of the ten houses
investigated are illustrated by the floor plans of the
living areas in Figures 1 through 10 at the end of the re-
port. Pertinent data on the materials used in the walls,
floors, and ceilings, the size of windows and doors, as
well as the age of the houses, and type of heating system
are shown in Tables 1 through 10 at the end of the report.

A summary of the more significant data on the materials
and dimensions for all the houses is shown in Table 11.
This table indicates that there were four brick, five frame,
and one stone building, of which six were one-story high
and four were two stories in height. Five buildings had
a basement, four had a crawl space, and one building was
built on a concrete slab-on-grade. There were four practi-
cally new houses, and the ages of the others ranged from
6 to 46 years, averaging 27 years. The heated floor area
of the buildings ranged from 598 square feet to 2,490
square feet, with an average of 1,427 square feet.

The total lengths of cracks around doors and windows are shown in this table.  These measurements were taken from the respective floor plans according to methods described in the ASHRAE "Guide" and were used in calculating the air infiltration values based on the crack length.

Table 11

Summary of Pertinent Data on Houses

| House Occupant | Material in Walls | No. of Stories | Foundation | Age years | Heated Floor Area sq ft | Crack Length, ft | | |
|---|---|---|---|---|---|---|---|---|
| | | | | | | Door | Windows | |
| | | | | | | | Single | Double |
| Hardy | Brick | 1 | Crawl sp. | 20 | 1220 | 57 | | 219 |
| Hufford | Frame | 1 | Basement | 30 | 1229 | 38 | 46 | 234 |
| Craig | Brick | 1 | Crawl sp. | New | 1510 | 38 | | 162 |
| Metzger | Frame | 2 | Basement | 20 | 1230 | 38 | 90 | 189 |
| Wrigley | Frame | 2 | Basement | 40 | 1510 | 76 | 126 | 126 |
| Spann | Stone | 1 | Basement | New | 1658 | 80 | | 226 |
| Yeiter | Frame | 1 | Crawl sp. | New | 1130 | 40 | | 162 |
| Dieckman | Frame | 2 | Crawl sp. | 46 | 1696 | 56 | 8 | 252 |
| Farnsley | Brick | 2 | Basement | New | 2490 | 39 | | 224 |
| Lunsford | Brick Apt. | 1 | Slab | 6 | 598 | 46 | | 68 |

### 3.  TEST METHOD AND PROCEDURE

Infiltration is defined as the air leakage of a building through cracks and interstices around doors and windows and through floors and walls that cannot be directly controlled by the occupants.  Ventilation includes the controlled displacement of air in a building through openings, such as windows, doors, ventilators, and combustion heating devices using either natural or mechanical motivation.  The magnitude of infiltration depends on the wind and temperature forces, and the structural design, workmanship, and condition of the building.

The air change rate of an enclosure is defined as the ratio of the hourly rate at which the air enters (or leaves) the enclosure to the volume of the enclosure.

The infiltration of air in each of the ten electrically heated houses was determined by the tracer gas method.[1] The apparatus used was the portable infiltration meter developed at the National Bureau of Standards.[2]  Approximately 1/2 percent of helium in relation to the total volume of the house was introduced after the test apparatus had been brought to a temperature equilibrium in the house. The helium was mixed with the room air by using several desk fans.  The outside doors and windows were closed, whereas closets and cupboards, and all inside doors were kept open, so the concentration of tracer gas would decay in these spaces at the same rate as in the living space. The ten sensing probes were placed near the centers of the rooms about 3 feet above floor level, and readings were taken at each probe station at 5-minute intervals for a period of 1 hour or more.  During the test, the indoor and outdoor temperatures were measured as well as the wind velocity and direction in the vicinity of the house about 10 feet above ground.  Two to four infiltration tests were made in each dwelling at prevailing conditions over a period of about 2 days.

[1] Marley, W. G., "The Measurement of the Rate of Air Change," Journal of the Institution of Heating and Ventilating Engineers, Vol. 2, 1935.

[2] Coblentz, C. W., and Achenbach, P. R., "Design and Performance of a Portable Infiltration Meter," Transactions, American Society of Heating and Air Conditioning Engineers, Vol. 63, 1957.

## 4. TEST RESULTS

A total of thirty infiltration tests were made. Two of these had to be omitted, however, because of significant changes in the infiltration rates during the test period, caused by opening of outside doors.

It was found that the most practical way of evaluating the readings of the infiltration meter was to plot them on semi-logarithmic graph paper. It can be shown that the air change rate in an enclosed space during a selected interval is directly proportional to the natural logarithm of the ratio of the concentration of the tracer gas at the beginning and end of the time interval, if the conditions remain constant. Thus, a constant infiltration rate would be represented by a straight line on semi-logarithmic graph paper.

The decay rate of the tracer gas at each station of observation during the twenty-eight tests made in the ten sample houses was plotted on semi-logarithmic graph paper to obtain an average air change rate, and to reveal the steadiness of the infiltration process. These data are shown in Figures 11 to 38 at the end of the report. Each figure shows the house identification, the location of each sensing element, and the computations used to determine the air change rate at each station and for the house as a whole.

In most instances, a straight line was a good representation of the decay curve. In the few cases where a straight line was not a good approximation of the decay curve, the data for these stations were not used in determining the average value for the house. The air change rate for the entire house was computed as the sum of the products of the infiltration rates in the individual rooms, and the corresponding percentage of the total house volume represented by each room. In cases where the infiltration data for a particular room was not usable, the volume of that room was not included in the total house volume. This procedure is tantamount to assuming that the infiltration rate of a room for which the data was not available or could not be used was equal to the average infiltration rate for the rest of the house.

Table 12 is a summary of the average infiltration rate for each test and shows the average wind velocity and prevailing direction, the inside-outside temperature difference, the observed air change rate, and an air change rate

converted to a 10 mph wind velocity and an indoor-outdoor temperature difference of 40°F. The method of converting the observed values to a constant wind velocity and temperature difference will be discussed later in this report.

## Table 12

### Summary of Average Infiltration Rates in Sample Houses

| House Occupant | Test Number | Approx. Avg. Wind Velocity mph | Prevail-ing Wind Direction | Indoor-Outdoor Temp. Diff. °F | Air Changes per Hour | | |
|---|---|---|---|---|---|---|---|
| | | | | | Observed | Converted to 10 mph 40°F | Average Converted |
| Hardy | 1 | 15 | SW | 45 | 0.84 | 0.67 | |
| | 2 | 15 | W | 45 | 0.77 | 0.62 | |
| | 3 | 15 | WNW | 48 | 0.77 | 0.60 | 0.63 |
| | 4 | 15 | W | 46 | 0.58 | 0.46 | 0.46* |
| Hufford | 5 | 6 | N | 42 | 0.71 | 0.81 | |
| | 6 | 6 | N | 43 | 0.56 | 0.63 | |
| | 7 | 11 | S | 43 | 0.91 | 0.85 | 0.76 |
| Craig | 8 | 11 | SW | 27 | 0.51 | 0.58 | |
| | 9 | 15 | SW | 23 | 0.42 | 0.43 | |
| | 10 | 10 | SSW | 23 | 0.35 | 0.44 | 0.48 |
| Metzger | 11 | 13 | SSW | 24.5 | 1.13 | 1.22 | |
| | 12 | 12 | SSW | 20 | 0.85 | 1.03 | |
| | 13 | 12 | SW | 29 | 0.67 | 0.71 | 0.99 |
| Wrigley | 14 | 11 | W | 41 | 0.94 | 0.87 | |
| | 15 | 10 | W | 41.5 | 0.80 | 0.78 | |
| | 16 | 6 | NW | 44 | 0.79 | 0.85 | |
| | 17 | 11 | N | 45.5 | 0.96 | 0.86 | 0.84 |
| Spann | 18 | 6 | WSW | 54.5 | 0.55 | 0.53 | |
| | 19 | 12 | WSW | 49.5 | 0.39 | 0.33 | |
| | 20 | 8 | WSW | 46 | 0.23 | 0.23 | 0.36 |
| Yeiter | 21 | 6 | NW | 48 | 0.59 | 0.62 | |
| | 22 | 6 | SW | 50 | 0.42 | 0.43 | 0.53 |
| Dieckman | 23 | 6 | NE - SW | 38 | 0.59 | 0.71 | |
| | 24 | 6 | SW | 42.5 | 0.63 | 0.71 | |
| | 25 | 8 | NW | 53 | 0.67 | 0.62 | 0.68 |
| Farnsley | 27 | 11 | W | 46 | 0.50 | 0.51 | 0.51 |
| Lunsford | 28 | 6 | NE | 42.5 | 0.58 | 0.65 | |
| | 30 | 8 | W | 63.5 | 0.81 | 0.66 | 0.66 |

* Closed exhaust vents in kitchen and bathroom.

The average wind velocities that prevailed during the air infiltration tests ranged from 6 to 15 mph, and the inside-outside temperature differences were between 21° and 53°F. This variation in conditions made it difficult to correlate the air change rate with the actual air tightness of the houses. Not enough tests were made with any one house to evaluate directly the effects of wind velocity and temperature difference on the infiltration rate so a direct comparison could be made between houses at a selected climatic condition.

An empirical formula was used, therefore, to convert the observed infiltration rates to a uniform condition of wind velocity and temperature difference that was near to the average of the observed test conditions. Published information[3],[4] on infiltration measurements in two test houses at the University of Illinois indicated that the air change rate in each was directly proportional to the indoor-outdoor temperature difference and to the wind velocity, and that the infiltration rate with no wind and no indoor-outdoor temperature difference ranged from 0.12 to 0.18 air change. The University of Illinois data further showed that an increase in wind velocity of 1 mph was equivalent to an increase of two or four degrees F in temperature difference in its effect on the infiltration rate. Thus, an equation of the form of equation (1) can be used to approximate the effect of wind and temperature difference on the air change rate.

$$A.C. = K (0.1 + 0.03W + 0.01T) \qquad (1)$$

where A.C. = hourly air change rate
      W = wind velocity, mph
      T = inside-outside temperature difference, °F
      K = a constant depending on the air tightness and height of the building.

[3] Bahnfleth, D. R., et al, "Measurement of Infiltration into Residences," Part I, Transactions, American Society of Heating and Air Conditioning Engineers, Vol. 63, 1957.

[4] Same as above, Part II.

A wind velocity of 10 mph and a temperature difference of 40°F were used as a basis for comparing the infiltration rate of the several houses since it approximated the mean of the observed conditions. Thus, the computed air change rate (A.C.') at this selected condition could be determined by equation (2).

$$A.C.' = \frac{0.1 + (0.03 \times 10) + (0.01 \times 40)}{0.1 + 0.03W + 0.01T} \times A.C. \qquad (2)$$

where, A.C., W, and T were the observed values in any given test.

Table 12 shows the air change rate for each test converted by equation (2) to a wind velocity of 10 mph and a temperature difference of 40°F. The table also shows the average converted value for all tests in each house. These converted values should be considered as approximate values because the absolute and relative values of the constants in equation (1) probably vary from house to house.

Table 13 summarizes the converted air change rates in relation to the type of building construction and foundation, and building height. It shows that the infiltration rate ranged from 0.36 to 0.99 air change under the same conditions. Since only one house in each category was tested, conclusions should not be drawn about categorical differences in air tightness of the different types of houses. The measured air infiltration rates of the two test houses[3],[4] at the University of Illinois for these same wind and temperature conditions was 0.40 for a two-story brick veneer house over a basement and 0.58 for a single-story frame house over a basement.

Table 13 shows two values for the converted air change rate of the Hardy house. The first value, 0.63, was the average of three tests made with the exhaust vents in the kitchen and bathroom open, whereas the second value, 0.46, was obtained with these vents closed. Since the volume of the Hardy house was 9,760 cubic feet, it appears that these two vents produced a combined ventilation of about 1,660 cubic feet per hour.

Table 13

Air Change Rates of Residences, Converted to
10 mph Wind Velocity and 40°F Temperature Gradient

| Type of Foundation | Wall Material | Number of Stories | |
|---|---|---|---|
| | | One | Two |
| Basement | Stone | 0.36 | |
| | Brick | 0.48 | 0.51 |
| | Frame | 0.76 | 0.99 |
| Crawl space | Brick | (0.63)(0.46)* | |
| | Frame | 0.53 | 0.68 |
| Slab-on-grade | Brick | 0.66 | |

* Closed exhaust vents in kitchen and bathroom.

The air infiltration of the buildings was also
calculated using the crack method as outlined in the
ASHRAE "Guide," 38th edition, 1960. For the purpose of
this computation, it was assumed that all windows were
weatherstripped, and a wind velocity of 15 mph was se-
lected. According to the "Guide," the infiltration rate
of 24 cubic feet per hour per foot of crack length for
single double-hung wood sash windows was halved for
double windows, and the air flow rate for doors was se-
lected at 55 cubic feet per hour per foot perimeter.
The value computed by this method for each of the houses
is shown in the third column of Table 14. The last two
columns in the table show the average values of observed
infiltration rates and of these rates converted to a wind
velocity of 10 mph and an inside-outside temperature
difference of 40°F.

It will be noted that there is a better than ± 10
percent agreement between the infiltration rates calculated
by the crack method and the converted values on seven of
the ten houses studied even though the infiltration compu-
tation by the crack method was based on a 15 mph wind and
does not take temperature difference into account as a
variable. The Spann residence shows a computed crack
length infiltration rate 50 percent higher than that con-
verted from the test results, and the infiltration of the
Dieckman residence as calculated by the crack method was
approximately 30 percent lower than the corresponding
converted value.

Table 14

Comparison of Air Change Rates Computed
by the Crack Method and Average Observed Values

| House Occupant | Description of Building | Computed by Crack Method for 15 mph Wind | Observed, Actual | Converted from Observed Data to 10 mph 40°F |
|---|---|---|---|---|
| Hardy | 1-story Brick, crawl space | 0.59 | 0.74 | 0.59 |
| Hufford | 1-story Frame, basement | 0.70 | 0.73 | 0.76 |
| Craig | 1-story Brick, basement | 0.53 | 0.43 | 0.48 |
| Metzger | 2-story Frame, basement | 0.94 | 0.88 | 0.99 |
| Wrigley | 2-story Frame, basement | 0.75 | 0.87 | 0.84 |
| Spann | 1-story Stone, basement | 0.54 | 0.39 | 0.36 |
| Yeiter | 1-story Frame, crawl space | 0.49 | 0.51 | 0.53 |
| Dieckman | 2-story Frame, crawl space | 0.47 | 0.68 | 0.68 |
| Farnsley | 2-story Brick, basement | 0.55 | 0.50 | 0.51 |
| Lunsford | 1-story Brick, on slab | 0.70 | 0.70 | 0.66 |

Table 1

E. Hardy Residence, Rt. 3, Greenfield

1-Story Brick House over Crawl Space
20 years old, Heated Floor Area 1220 ft$^2$

**Walls:**
4" Brick
3 5/8" Studs
1/2" Plaster and Rock Lath
.002" Vapor Barrier

**Ceiling (open):**
1/2" Plaster and Rock Lath
2" x 6" Joists

**Floor:**
1" x 6" and 8" Subflooring
3/8" Plywood, with Vinyl Tile over
.002" Vapor Barrier

**Insulation:**
Walls   - Double-Blown Cellulose Fiber
Ceiling - Loose Cellulose Fiber
Floor   - 3 1/2" Cellulose Fiber Batts

**Roof:**
Pitch    - 5'-2"/16'-6"
Height   - 8'-0"
Overhang - 18"
Louvers  - Twelve, 4" x 12"

**Basement:**
None (crawl space)

**Windows:**
Double-hung, wood sash, with aluminum storm, caulked,
    sealed double glass in living room

**Doors:**
Side (to garage) - Solid wood
Rear             - Wood with 1/2 glass, with storm
Front            - Wood, with storm

**Heating:**
Electric baseboard

Table 2

T. E. Hufford Residence, Rt. 1, Charlottsville

1-Story Frame House over Basement
30 years old, Heated Floor Area 1229 ft$^2$

Walls:
    1/2" Wood Lap Siding
    Building Paper
    1" Sheathing
    2" x 4" Studs
    1" Plaster and Wood Lath

Ceiling:
    1" Plaster and Wood Lath
    2" x 6" Joists
    1" Wood Flooring (except over living room)

Floor:
    1" Pine Finish (no subflooring)
    2" x 6" Joists

Insulation:
    Walls   - 4" Rock Wool
    Ceiling - 4" Rock Wool, 2" Cellulose Fiber
    Floor   - None

Roof:
    Pitch   - 4/12
    Louvers - One, 4" x 12", two, 4" x 8"

Basement:
    Full, except under porch, no insulation or vapor barrier;
      walls are cement block to ground level with brick above
      to house frame; unheated

Windows:
    Wood sash, storm windows in bedroom 2 and center sash of
      bedroom 1 only, in attic there are 3 windows (front,
      rear, north)

Doors:
    Wood with 1/2 glass and storm to front and carport

Heating:
    Electric baseboard

## Table 3

### J. S. Craig Residence, RR. 1, Wabash

1-Story Brick with Basement and Crawl Space
New House, Heated Floor Area 1510 ft$^2$

Walls:
    4" Brick Veneer
    1" Sheathing
    2" x 4" Studs
    1/2" Plaster and Rock Lath
    Vapor Barrier

Ceiling:
    1/2" Plaster and Rock Lath
    2" x 6" Joists
    Vapor Barrier

Floor:
    5/8" Finish Flooring
    3/4" Subflooring
    2" x 10" Joists
    1/2" Plaster and Rock Lath

Insulation:
    Walls   - 4" Cellulose Fiber
    Ceiling - 6" Cellulose Fiber
    Floor   - 2" Batts (Alfol)

Roof:
    Pitch       - 4/12
    Overhang    - 24"
    Eave Vents  - Twelve, 8" x 12"
    Exhaust Fans

Basement:
    Under kitchen, living room, dining room; plastered
      ceiling, cement block walls, concrete floor; rest
      is crawl space open to basement

Windows:
    Casement with storm in bedroom 1, dining room,
      kitchen, casement with storm in baths, bedroom 2,
      sealed double glass in living room, four 12" x 15"
      single pane in basement

Doors:
    Combination aluminum in front; all others solid wood

Heating:
    Electric ceiling cable

Glass doors in fireplace

## Table 4

D. A. Metzger Residence, RR. 3, N. Manchester, Ind.

2-Story Frame with Cinder Block Basement
20 years old, Heated Floor Area 1230 ft$^2$

Walls:
    1/4" Asbestos Shingles
    Building Paper
    1" Wood Sheathing
    2" x 4" Studs
    1/2" Plaster and Lath

Ceiling (open):
    1st Floor (8')
        1/2" Plaster and Lath
        2" x 6" Joists
        1" Subflooring

    2nd Floor (7 1/2')
        1/2" Plaster and Lath
        2" x 6" Joists

Floor:
    1/2" Finish (Pine)
    1/2" Subflooring (Pine)
    2" x 8" Joists

Insulation:
    Walls    - 3 5/8" Blown Cellulose Fiber
    Ceiling - 6" Blown Cellulose Fiber
    Floor    - 2" Batts (Alfol), "U" is .04

Roof:
    Pitch    - 4/12
    Overhang - 24"
    Louvers  - Four, 4" x 12"

Basement:
    Under kitchen and bedroom 1, other area is crawl space,
        walls are concrete block with two 18" x 24" casement
        windows; crawl space opens into basement; unheated

Windows:
    Wood sash, no storm in living room towards porch; wood
        sash with storm on all other rooms

Doors:
    Wood with 1/2 glass

Heating:
    Electric baseboard

Exhaust fans in bathroom and kitchen

## Table 5

R. Wrigley Residence, Rt. 3, Warsaw, Ind.

2-Story Frame House over Basement
40 years old, Heated Floor Area, 1510 ft$^2$

Walls:
    1/4" Asbestos Siding
    5/8" Wood Sheathing
    2" x 4" Studs
    1" Plaster and Lath

Ceiling (open):
    1st Floor (9')
        1" Plaster and Lath
        2" x 6" Joists
        1" Flooring

    2nd Floor (8')
        1" Plaster and Lath
        2" x 6" Joists

Floor:
    1" Flooring
    1/2" Subflooring
    2" x 8" Joists

Insulation:
    Walls   - 3 5/8" Blown Cellulose Fiber
    Ceiling - 6" Blown Cellulose Fiber, and 4" Rock Wool,
            10 years old
    Floor   - 3 5/8" Cellulose Fiber Batts

Roof (Asbestos Shingles):
    Pitch       - 1/2
    Overhang   - 18"
    Louvers    - Six, 10" x 10"
    Exhaust Fans - 1 in kitchen

Basement:
    Full, except for crawl space under porches and office;
      poured cement walls, five 12" x 18" casement windows;
      unheated

Windows:
    Wood, single pane, with storm windows on first floor only

Doors:
    Wood, with storm door on west entrance

Heating:
    Electric baseboard

Table 6

M. Spann Residence, RR. 1, Pierceton

1-Story Stone Veneer over Basement
New House, Heated Floor Area 1658 ft$^2$

Walls:
      4" Stone Veneer
      1" Sheathing
      2" x 4" Studs
      1/2" Plaster and Rock Lath

Ceiling:
      1/2" Plaster and Rock Lath
      2" x 8" Joists

Floor:
      1/2" Pine Finish
      1/2" Subflooring (Pine)
      2" x 10" Joists

Insulation:
      Walls    - 3 1/2" Foil Backed Fiber Glass
      Ceiling - 6" Fiber Glass, 4" Cellulose Fiber
      Floor    - 3 1/2" Foil Backed Fiber Glass

Roof (Wood Shingles):
      Pitch    - 4 1/2 /12
      Overhang - 2'-6"
      Louvers  - Two, 12" x 24"

Basement:
      12" Cement Block Walls
      8" Poured Cement Floor
      Height - 7 1/2'

Windows:
      Sealed double glass throughout

Doors:
      Solid wood with storm on east side, sliding double
        glass door on west side, 2 wood with 1/2 glass
        and storm on south side

Heating:
      Electric cable (ceiling panel)

Exhaust fans in kitchen and bathroom

Table 7

B. Yeiter Residence, RR. 4, Warsaw

1-Story Frame House over Crawl Space
New House, Heated Floor Area 1130 ft$^2$

Walls:
    1/2" Redwood Cap Siding
    Aluminum Foil
    1" Ship Lap Siding (Pine)
    2" x 4" Studs
    Vapor Barrier
    1/2" Plaster and Rock Lath

Ceiling:
    1/2" Plaster and Rock Lath
    2" x 6" Joists
    Height - 7'-6"

Floor:
    Tile
    1/4" Building Board Underlay
    1" Ship Lap (Pine)
    2" x 10" Joists
    Vapor Barrier

Insulation:
    Walls   - 3 5/8" Cellulose Fiber
    Ceiling - 6" Cellulose Fiber
    Floor   - 3" Rock Wool

Roof (Asphalt Shingles):
    Pitch   - 4/12
    Overhang - 24"
    Louvers  - Two, 270 sq in.

Basement:
    None; crawl space, 2' high open crawl space with
      vapor barrier on ground

Windows:
    Sealed double glass throughout

Doors:
    Solid wood with storm

Heating:
    Electric baseboard

Table 8

W. Dieckman Residence, RR., Greenburg, Ind.

2-Story Frame House over Crawl Space
46 years old, Heated Floor Area 1696 $ft^2$

**Walls:**
 1/2" Wood Lap Siding
 3/4" Wood Sheathing
 2" x 4" Studs
 1" Plaster and Wood Lath

**Ceiling:**
 1st Floor (9'4")
  1" Plaster and Wood Lath
  2" x 6" Joists
  1" Flooring

 2nd Floor (7'-6")
  1" Plaster and Wood Lath
  2" x 6" Joists

**Floor:**
 1/2" Oak Finish
 1/2" Subflooring
 2" x 10" Joists

**Insulation:**
 Walls  - 3 5/8" Blown Cellulose Fiber
 Ceiling - 6" Blown Cellulose Fiber
 Floor  - None, and none between 1st and 2nd floors

**Roof:**
 Pitch  - 1/2
 Louvers - Two, 6" x 6", and three, 12" x 12"

**Basement:**
 None (crawl space), 18" clearance; two, 12" x 24"
  openings

**Windows:**
 Wood sash with storm in heated spaces, except there
  is no storm on first floor closet window

**Doors:**
 Wood with 1/2 glass, with aluminum storm on all except
  door to unheated porch which is an aluminum storm door

**Heating:**
 Baseboard

No vapor barrier; exhaust fan in kitchen

## Table 9

C. Farnsley Residence, Georgetown, Ind.

2-Story Brick House over Basement
New House, Heated Floor Area 2490 ft$^2$

**Walls:**
    4" Brick Veneer
    Building Paper
    3/4" Storm Sheathing
    2" x 4" Studs
    Vapor Barrier
    3/4" Plaster and Rock Lath

**Ceiling:**
    1st Floor (8')
        1/2" Plaster and Rock Lath
        2" x 8" Joists
        3/4" Subflooring
        1/4" Masonite

    2nd Floor (6 1/2')
        1/2" Plaster and Rock Lath
        2" x 6" Joists

**Floor:**
    1/4" Masonite
    3/4" Subflooring (Fir)
        2" x 4" Joists

**Insulation:**
    Walls   - 3 5/8" Blown Cellulose Fiber
    Ceiling - 1st Floor (8'); 7 5/8" Blown Cellulose Fiber
              2nd Floor (6 1/2'); 6" Blown Cellulose Fiber
                and 3 5/8" between rafters
    Floor   - None

**Roof:**
    Pitch    - 8/12
    Overhang - None
    Louvers  - Four, 72-sq-in. triangles

**Windows:**
    Aluminum with storm

**Doors:**
    Front - Solid wood with storm
    Side  - Wood with 1/2 glass, no storm

**Vapor Barrier:**
    Placed in floor, wall and ceiling

Exhaust fan in kitchen

Table 10

R. E. Lunsford Residence, W. Campbell St., Indianapolis, Ind.

1-Story Brick Apartment over Concrete Slab
6 years old, Heated Floor Area 598 ft$^2$

Walls:
     4" Brick Veneer
     1" Sheathing
     2" x 4" Studs
     Vapor Barrier
     1/2" Plaster and Rock Lath

Ceiling:
     1/2" Plaster and Rock Lath
     2" x 6" Joists
     Height - 8'

Floor:
     5" Thick Concrete Slab

Insulation:
     Floor    - 1" Fiber Glass Board Perimeter Insulation
                 (2' down and 2' in)
     Ceiling - 6" Blown Glass Fiber
     Walls    - 3 5/8" Fiber Glass Batts

Roof (Asphalt Shingles):
     Pitch    - 2/12
     Overhang - 12"

Windows:
     Sealed double glass

Doors:
     North - Wood with 1/2 glass and storm
     South - Sliding, double glass

GARAGE
UNHEATED

EUGENE HARDY
RT 3, GREENFIELD, IND.
I STORY BRICK OVER
CRAWL SPACE , 20 YRS. OLD

22' 6"

15' 8"

8' 10"

5' 8"

KITCHEN

9' 0"

LIVING
ROOM

UTILITY

8' 0"

BATH

6' 10"

FRONT

25' 8"

14' 10"

3' 1"

9' 9"

5"

BEDROOM
3

10' 6"

C.    C.    C.

2' 0"

5"

C.    C.

2' 0"

BEDROOM
1

14' 0"

BEDROOM
2

10' 0"

14' 10"

13' 3"

N

OFFICE

11'0"

6'11"

DOWN

2'2"

C.

11'9"

BEDROOM 2

10'6"

UP

C.

7'0"

BATH

5'1"

20'5"

KITCHEN

9'4"

C.

BEDROOM 1

11'4"

11'10"

5'0"

13'8"

15'6"

LIVING ROOM

15'6"

29'4"

FRONT

N

T.E. HUFFORD
RR I, CHARLOTTESVILLE, IND.
I STORY FRAME OVER BASEMENT,
30 YEARS OLD

DINING ROOM

13'4"

14'8"

10'0"

15'9"

LIVING ROOM

BEDROOM 3

C.

BEDROOM 2

STOVE

11'0"

C.

11'0"

23'0"

KITCHEN

4'0"

BATH 2

7'0"

WASH ROOM

C.

C.

5'0"

14'8"

BEDROOM 1

BATH 1

11'8"

LAUNDRY

DOWN

15'0"

9'1"

FRONT

GARAGE UNHEATED

N

JAMES S. CRAIG
RR. WARBASH, IND.
I STORY BRICK VENEER
WITH BASEMENT AND
CRAWL SPACE, NEW

## 2 ND FLOOR

BEDROOM 2

8'10"

C.

C.

BEDROOM 4

12'4"

7'0"

DOWN

9'0"

STORAGE UNHEATED

C.

BEDROOM

12'6"

13'5"

3'0"

10'6"

DONALD A. METZGER
RR # 3, N. MANCHESTER, IND.
2 STORY FRAME OVER
BASEMENT, 20 YEARS OLD

FRONT

PORCH UNHEATED

10'9"

12'3"

KITCHEN

13'5"

13'6"

9'7"

11'7"

8'0"

BATH

5'7"

3'6"

DOWN

UP

LIVING ROOM

25'3"

PORCH UNHEATED

9'6"

BEDROOM 1

1 ST FLOOR

N

**2 ND FLOOR**

BEDROOM 2 — 10'9", 8'4"
C. — 2'6"
BEDROOM 3 — 10'9", 12'6"
BATH — 6'0"
C.
C.
HALL
C. — 2'10"
BEDROOM 1 — 14'0", 8'9"
DOWN — 6'1"
BEDROOM 4 — 13'0", 10'9"

N

RALPH WRIGLEY
RT # 3, WARSAW IND.
2 STORY FRAME OVER
BASEMENT, 40 YEARS OLD

OFFICE — 8'11", 7'7"
DINING ROOM — 12'9", 15'0"
LINING ROOM — 13'4"
PORCH OPEN — 9'7"
LAV. — 5'3"
PORCH UN-HEATED — 13'9"
KITCHEN — 13'9"
TO BASEMENT
UP
C.
FRONT

1 ST FLOOR

MAYNARD SPANN
PIERCETON, IND.
1 STORY STONE VENEER
OVER BASEMENT, NEW

FRONT

KITCHEN

11'0"

26'9"

LAUNDRY

6'6"     4'0"

5'0"

4'9"

BATH

11'4"

DEN

14'0"

1' STEP

1' STEP

LIVING ROOM

18'0"

26'0"

1' STEP

12'0"

BEDROOM
3

10'6"

C.

C.

BEDROOM
1

15'6"

C.

12'0"

C.

BATH

C.

4'0"

8'0"

12'0"

C.

BEDROOM
2

10'0"

GARAGE UNHEATED

21'4"

N

PUMP ROOM          LAUNDRY

4'0"

7'0"

FRONT

DINING ROOM

20'0"

LIVING ROOM

22'0"

16'0"          8'6"

BERYL YEITER
RR 4, WARSAW, IND.
I STORY FRAME OVER
CRAWL SPACE, NEW

KITCHEN

C.

C.

BEDROOM 1

10'0"

BATH

5'11"

BEDROOM 2

12'0"

BEDROOM 3

C.   C.

12'0"

10'0"     2'   2'    10'0"

WILBUR DIECKMAN
RR, GREENBURG, IND.
2 STORY FRAME OVER
CRAWL SPACE, 46 YRS. OLD

2 ND FLOOR

1 ST FLOOR

FRONT

**2nd Floor:**

BEDROOM 4

C.

C.

BEDROOM 3

15'4"

15'4"

15'4"

BEDROOM 2

15'2"

6'4"

15'8"

DOWN

STORAGE UN-HEATED

N

**1st Floor:**

LIVING ROOM

15'4"

15'4"

15'4"

DINING ROOM

6'6"

PORCH UN-HEATER

15'4"

BATH

5'10"

11'6"

BEDROOM 1

UP

15'6"

KITCHEN

15'8"

C.

C.

Figure 6

## SECOND FLOOR

STORAGE AREA

BATH 2 — 9' 0"

9' 0"

STORAGE AREA

UPSTAIRS

12' 0"

DOWN

STORAGE

STORAGE

STORAGE

CHARLES FARNSLEY
RR 2, GEORGETOWN, IND.
2 STORY BRICK OVER BASEMENT, NEW

## FIRST FLOOR

11' 1"    2' 8"    6' 3"    2' 9"    10' 2"    8' 5"

BEDROOM 1    C.    BATH    C.    5"    BEDROOM 2    OFFICE

15' 3"

C.    C.    1' 10"    3' 10"

UP    DOWN

19' 3"    4"    23' 5"

LIVING ROOM    15' 3"    KITCHEN

15' 3"    15' 3"

32' 5"

44' 6"

FRONT

DINING ROOM

KITCHEN

6'0"

STORAGE

NOTE:
WALL ADJOINING
HEATED APT.

7'0"        3'7"

BATH

5'0"

26'0"

LIVING
ROOM

BEDROOM

10'0"

11'6"        11'0"

FRONT

R.E. LUNSFORD
W. CAMPBELL ST.
INDIANAPOLIS, IND.
1 STORY BRICK VENEER
APT. ON SLAB, 6 YRS. OLD

Figure 16

E. HARDY RESIDENCE, RT. 3, GREENFIELD
BRICK HOUSE OVER CRAWL SPACE

TEST NO. 1
NOV. 29, 1960

1  $B_2$ $LN(93/52) = .58$

2  $LR$ $LN(87/39) = .80$

3  $B_3$ $LN(83/43) = .66$

4  $B_1$ $LN(95/48) = .68$

5  $B_1$ $LN(86/35) = .90$

6  $LR$ $LN(96/34) = 1.04$

7  UTIL $LN(100/58) = .54$

| SPACE | FT² | % TOTAL | |
|---|---|---|---|
| LR | 385 | 34.0 | .31 |
| $B_1$ | 229 | 20.2 | .16 |
| $B_2$ | 142 | 12.5 | .07 |
| $B_3$ | 112 | 9.9 | .06 |
| BATH | 67 | 5.9 | .06 |
| UTIL | 78 | 6.9 | .04 |
| KIT | 120 | 10.6 | .14 |
| | | | .84 |

WEIGHTED AIR
CHANGE PER HOUR

8 BATH $LN(85/30) = 1.04$

9 KIT $LN(73/20) = 1.30$

10 LR OMIT

TIME, MINUTES

10   20   30   40   50   60

Figure 11

E. HARDY RESIDENCE, RT. 3, GREENFIELD
BRICK HOUSE OVER CRAWL SPACE

TEST NO. 2
NOV. 29, 1960

1 $B_2$ LN (95/58) = .49
2 LR LN (99/46) = .77
3 $B_3$ LN (89/63) = .35

4 $B_1$ LN (93/51) = .60
5 $B_1$ OMIT
6 LR LN (90/29) = 1.10
7 UTIL LN (87/36) = .89

| SPACE | FT² | % | TOTAL |
|---|---|---|---|
| LR | 385 | 34.0 | .32 |
| $B_1$ | 229 | 20.2 | .12 |
| $B_2$ | 142 | 12.6 | .06 |
| $B_3$ | 112 | 9.9 | .03 |
| BATH | 67 | 5.9 | .06 |
| UTIL | 78 | 6.9 | .06 |
| KIT | 120 | 10.6 | .12 |
| | 1133 | | .77 |

WEIGHTED AIR
CHANGE PER
HOUR

8. BATH LN (82/79) = 1.04
9 KIT LN (83/25) = 1.26
10 LR LN (92/35) = .97

TIME, MINUTES

Figure 12

E. HARDY RESIDENCE, RT. 3 GREENFIELD
BRICK HOUSE OVER CRAWL SPACE

TEST NO. 3
NOV. 29, 1960

1  $B_2$  $LN\left(\frac{96}{58}\right) = .52$

2  LR  $LN\left(\frac{92}{41}\right) = .80$

3  $B_3$  OMIT

7  UTIL  $= .52$

4 $B_1$  $LN\left(\frac{103}{57}\right) = .58$

5 $B_1$  $LN\left(\frac{104}{44}\right) = .86$

6 LR  $LN\left(\frac{96}{32}\right) = 1.10$

| SPACE | FT.$^2$ | %0 TOTAL | |
|---|---|---|---|
| LR | 385 | 37.7 | .35 |
| $B_1$ | 229 | 22.4 | .16 |
| $B_2$ | 142 | 13.9 | .07 |
| $B_3$ | | | .05 |
| BATH | 67 | 6.6 | .05 |
| UTIL | 78 | 7.6 | .04 |
| KIT | 120 | 11.8 | .10 |
| | 1021 | | 77 |

WEIGHTED AIR
CHANGE PER
HOUR

8 BATH  $LN\left(\frac{92}{44}\right) = .73$

9 KIT  $LN\left(\frac{78}{34}\right) = .83$

10 LR  $LN\left(\frac{99}{42}\right) = .86$

10    20    30    40    50    60

TIME, MINUTES

Figure 13

# E. HARDY RESIDENCE, RT. 3, GREENFIELD
## BRICK HOUSE OVER CRAWL SPACE

TEST NO. 4
NOV. 30, 1960.

Figure. 14

$1 \ B_2 \ LN \left(\frac{79}{45}\right) = .56$

$4 \ B_1 \ LN \left(\frac{93}{54}\right) = .54$

$5 \ B_1 \ LN \left(\frac{89}{57}\right) = .45$

$2 \ LR \ LN \left(\frac{105}{68}\right) = .44$

$3 \ B_3 \ LN \left(\frac{96}{49}\right) = .67$

$6 \ LR \ LN \left(\frac{106}{60}\right) = .57$

$7 \ UTIL \ LN \left(\frac{82}{42}\right) = .67$

| SPACE | FT.$^2$ | % TOTAL | |
|-------|------|---------|------|
| LR | 385 | 36.1 | .20 |
| B₁ | 229 | 21.5 | .11 |
| B₂ | 142 | 13.3 | .08 |
| B₃ | 112 | 10.5 | .07 |
| UTIL | 78 | 7.3 | .05 |
| KIT | 120 | 11.3 | .07 |
| | 1066 | | .58 WEIGHTED |

AIR CHANGE PER HOUR

$8 \ BATH \ OMIT$

$9 \ KIT \ LN \left(\frac{77}{41}\right) = .63$

$10 \ LR \ LN \left(\frac{102}{59}\right) = .55$

TIME, MINUTES

T.E. HUFFORD RESIDENCE, RT. 1 CHARLOTTESVILLE
FRAME HOUSE OVER BASEMENT

TEST No. 5
DEC. 1, 1960

1 KIT    OMIT
2 $B_2$ LN $(82/44)$ = .62
3 KIT LN $(87/47)$ = .62
4 LR LN $(80/40)$ = .69

5 $B_1$ LN $(79/42)$ = .63
6 $B_2$ LN $(84/39)$ = .77
7 BATH LN $(92/56)$ = .50

| SPACE | FT.$^2$ | % TOTAL | |
|---|---|---|---|
| LR | 454 | 38.5 | .32 |
| KIT | 264 | 22.4 | .14 |
| $B_1$ | 202 | 17.1 | .10 |
| $B_2$ | 147 | 12.5 | .07 |
| BATH | 35 | 3.0 | .02 |
| OFFICE | 76 | 6.5 | .04 |
| | 1178 | | .71 |

WEIGHTED AIR
CHANGE PER HOUR

8 OFFICE LN $(82/46)$ = .58
9 $B_1$ LN $(73/44)$ = .58
10 LR LN $(68/26)$ = .96

TIME  MINUTES

Figure 15

T.E. HUFFORD RESIDENCE, RT. 1, CHARLOTTSVILLE
FRAME HOUSE OVER BASEMENT

TEST NO. 6
DEC. 1, 1960

1 KIT LN (90/59) = .42
2 B₂ LN (79/36) = .79
3 KIT LN (91/56) = .49

4 LR LN (90/56) = .48
5 B₁ LN (99/56) = .57
6 B₂ LN (107/45) = .87

| SPACE | FT² | % TOTAL | |
|---|---|---|---|
| LR | 454 | 38.5 | .22 |
| KIT | 264 | 22.4 | .10 |
| B1 | 200 | 17.1 | .09 |
| B2 | 147 | 12.5 | .10 |
| BATH | 35 | 3.0 | .02 |
| OFFICE | 76 | 6.5 | .03 |
| | 1178 | | .56 |

WEIGHTED AVE
CHANGE PER
HOUR

7 BATH LN (108/63) = .54
8 OFF LN (93/58) = .47
9 B1 LN (99/60) = .50
10 LR LN (85/43) = .68

CONCENTRATION PPM — K H₂ → V

TIME, MINUTES

Figure 16

T.E. HUFFORD RESIDENCE, RT 1, CHARLOTTSVILLE
FRAME HOUSE OVER BASEMENT

TEST NO. 7
DEC 2, 1960

1 KIT LN(51/49) = .50
2 B₂ LN(90/42) = .76
3 KIT OMIT
4 LR LN(73/43) = .53

5 B₁ LN(68/21) = 1.17
6 B₂ LN(80/25) = 1.16
7 BATH LN(89/44) = .71

| SPACE | FT² | % TOTAL | |
|---|---|---|---|
| LR | 454 | 38.5 | .39 |
| KIT | 264 | 22.4 | .11 |
| B₁ | 202 | 17.1 | .21 |
| B₂ | 147 | 12.5 | .72 |
| BATH | 35 | 3.0 | .02 |
| OFF | 76 | 6.5 | .06 |
| | 1178 | | .91 |

WEIGHTED AIR
CHANGE PER HOUR

9 B₁ LN(67/18) = 1.32
10 LR LN(61/14) = 1.47
OFFICE LN(70/29) = .89

TIME, MINUTES

Figure 17

J. S. CRAIG RESIDENCE, RR. 1, WABASH
BRICK HOUSE WITH BASEMENT AND CRAWL SPACE

TEST NO. 8
DEC 3, 1960

5 BATH, LN (95/64) = .40
9 KIT LN (95/47) = .71
10 KIT OMIT

1 B, OMIT
2 B3 LN (110/70) = .45
3 BATH2 LN (101/67) = .41
4 B2 LN (125/87) = .36

| SPACE | FT.$^2$ | %TOTAL | |
|-------|------|--------|------|
| LR | 338 | 29.9 | .14 |
| KIT | 306 | 27.1 | .19 |
| LAUND | 35 | 3.1 | .02 |
| B2 | 153 | 15.6 | .05 |
| B3 | 127 | 11.2 | .05 |
| BATH1 | 106 | 9.4 | .04 |
| BATH2 | 64 | 5.7 | .02 |
| | 1129 | | .51 |

WEIGHTED AIR
CHANGE PER HOUR
(6,7)

6 LR LN (100/62) = .48
7 LR LN (100/62) = .48
8 LAUND LN (94/57) = .50

CONCENTRATION, RELATIVE

TIME, MINUTES

Figure 18

# J.S. CRAIG RESIDENCE, RR.1, WABASH
## BRICK HOUSE WITH BASEMENT AND CRAWL SPACE



TEST NO. 9
DEC. 12, 1960

1 BR LN (90/49) = .61
3 BATH₂ LN (88/54) = .49
4 B2 LN (87/62) = .34
6 LR LN (74/49) = .41

2 B3 LN (97/54) = .59
5 BATH₁ LN (90/68) = .28
7 KIT LN (75/52) = .37

| SPACE | FT.² | % TOTAL | |
|-------|------|---------|------|
| LR | 338 | 25.0 | .01 |
| KIT | 306 | 22.7 | .08 |
| LAUN | 35 | 2.6 | .01 |
| B1 | 221 | 16.4 | .10 |
| B2 | 153 | 11.3 | .04 |
| B3 | 127 | 9.4 | .06 |
| BATH1 | 106 | 7.9 | .02 |
| BATH2 | 64 | 4.7 | .02 |
| | 1350 | | .42 |

(WEIGHTED)
AIR CHANGE
PER HOUR

8 LAUN LN (80/55) = .38
9 LR LN (85/61) = .22
10 KIT OMIT

TIME, MINUTES

Figure 19

TEST NO. 10
DEC 4, 1960

1 B1 $LN(94/68) = .32$
2 B3 $LN(91/66) = .32$
3 BATH₂ $LN(91/66) = .3$

4 B2 $LN(92/68) = .30$
5 BATH₁ $LN(81/50) = .48$
6 LR $LN(80/56) = .36$

| SPACE | FT² | %TOTAL | |
|---|---|---|---|
| LR | 338 | 25.0 | .09 |
| KIT | 306 | 22.7 | .08 |
| LAUN | 35 | 2.6 | .01 |
| B1 | 221 | 16.4 | .05 |
| B2 | 153 | 11.3 | .03 |
| B3 | 127 | 9.4 | .03 |
| BATH1 | 106 | 7.8 | .04 |
| BATH2 | 64 | 4.7 | .02 |
| | 1350 | | .35 |

WEIGHTED
AIR CHANGE
PER HOUR

7 LR $LN(82/50) = .31$
8 LAUN $LN(77/58) = .28$
9 KIT $LN(87/60) = .37$
10 KIT OMIT

TIME, MINUTES

Figure 20

D.A. METZGER RESIDENCE, RR.3, N. MANCHESTER.
FRAME HOUSE WITH BASEMENT AND CRAWL SPACE

TEST NO. 11
DEC 5, 1960

○1 BATH   LN(83/30) = 1.02
△2    LR  LN(75/29) = .95
+3    LR  LN(75/28) = .99
□4    KIT     OMIT

5  B₂  LN(100/25) = 1.39
6  B₃  LN(95/23) = 1.42
7  B₄  LN(91/27) = 1.22

| SPACE | FT² | % TOTAL | |
|---|---|---|---|
| LR | 342 | 32.5 | .32 |
| B₁ | 127 | 12.0 | .09 |
| B₂ | 130 | 12.3 | .17 |
| B₃ | 163 | 15.5 | .22 |
| B₄ | 153 | 14.5 | .18 |
| HALL | 94 | 8.9 | .11 |
| BATH | 45 | 4.3 | .04 |
| | 1054 | | 1.13 |

WEIGHTED AIR CHANGES
PER HOUR

10  B₁  OMIT
8   B₁  LN(92/43) = .76
9   HALL LN(81/24) = 1.29

TIME, MINUTES

Figure 21

# D.A. METZGER RESIDENCE, RR.3, N.MANCHESTER
## FRAME HOUSE WITH BASEMENT AND CRAWL SPACE

TEST NO. 12
DEC. 5, 1960

1 BATH  $LN(70/24) = 1.07$
2 LR  $LN(67/20) = 1.21$
3 LR  OMNT
4 KIT  $LN(76/40) = .64$

5 $B_2$  $LN(83/43) = .66$
6 $B_3$  $LN(96/45) = .76$
7 $B_4$  $LN(93/50) = .62$

| SPACE | FT.$^2$ | % TOTAL | |
|---|---|---|---|
| LR | 342 | 28.0 | .34 |
| KIT | 165 | 13.5 | .09 |
| B1 | 127 | 10.4 | .08 |
| B2 | 130 | 10.7 | .07 |
| B3 | 168 | 13.4 | .10 |
| B4 | 153 | 12.0 | .08 |
| HALL | 94 | 7.7 | .05 |
| BATH | 45 | 3.7 | .04 |
| | 1219 | | .85 |

WEIGHTED AIR CHANGE
PER HOUR

8  B1  $LN(86/38) = .82$
9 HALL  $LN(93/41) = .65$
10  B1  $LN(76/40) = .74$

TIME, MINUTES

Figure 22

TEST NO. 13
DEC. 6, 1960

1  BATH LN (87/40) = .78
2  LR LN (83/48) = .55
3  LR  OMIT
4  KIT LN (74/35) = .69

O 5 $B_2$ LN (84/43) = .67
Δ 6 $B_3$ LN (97/45) = .70
+ 7 $B_4$ LN (93/49) = .64

| SPACE | $FT^2$ | % TOTAL | |
|-------|--------|---------|------|
| LR | 342 | 28.0 | .154 |
| KIT | 165 | 13.5 | .093 |
| $B_1$ | 127 | 10.4 | .057 |
| $B_2$ | 130 | 10.7 | .072 |
| $B_3$ | 163 | 13.4 | .094 |
| $B_4$ | 153 | 12.6 | .081 |
| HALL | 94 | 7.7 | .061 |
| BATH | 45 | 3.7 | .030 |
| | 1219 | | .672 |

WEIGHTED AIR CHANGE
PER HOUR

O 8  $B_1$ LN (85/37) = .83
Δ 9  HALL (88/40) = .79
+ 10 $B_1$ LN (94/43) = .78

TIME, MINUTES

CONCENTRATION, PER CENT

Figure 23

R. WRIGLEY RESIDENCE, R.R. 3, WARSAW
FRAME HOUSE OVER BASEMENT

TEST NO 14
DEC 7, 1960

1 $B_1$  $LN(85/42) = .70$
2 LR  $LN(79/34) = .84$
3 $B_2$  OMIT
4 $B_3$  $LN(81/27) = 1.10$

5 $B_4$  $LN(81/22) = 1.30$
6 BATH $LN(89/34) = .96$
7 KIT $LN(83/31) = .99$

| SPACE | FT² | %TOTAL | |
|-------|-----|--------|-----|
| LR | 339 | 27.6 | .23 |
| KIT | 138 | 11.2 | .11 |
| $B_1$ | 123 | 10.0 | .07 |
| $B_3$ | 145 | 11.8 | .13 |
| $B_4$ | 169 | 13.8 | .18 |
| DR | 192 | 15.6 | .13 |
| OFF | 68 | 5.5 | .05 |
| BATH | 53 | 4.3 | .04 |
| | 1227 | | .94 WEIGHTED |

AIR CHANGE
PER HOUR

10 LR OMIT
8 DR  $LN(84/37) = .82$
9 OFFICE $LN(73/29) = .92$

TIME, MINUTES

Figure 24

# R. WRIGLEY RESIDENCE, RR.3, WARSAW
## FRAME HOUSE OVER BASEMENT



TEST NO. 15
DEC. 7, 1960

1 $B_1$    $LN(86/43) = .69$
2 LR    $LN(67/33) = .71$
3 $B_2$    OMIT
4 $B_3$    $LN(81/49) = .50$

O 5    $B_4$    $LN(87/31) = 1.03$
Δ 6 BATH $LN(81/40) = .71$
+ 7    KIT $LN(73/35) = .74$

| SPACE | FT.$^2$ | %TOTAL | |
|-------|------|--------|------|
| LR | 339 | 27.6 | .20 |
| $B_1$ | 123 | 10.0 | .07 |
| $B_3$ | 145 | 11.8 | .06 |
| $B_4$ | 167 | 13.8 | .14 |
| DR | 192 | 15.6 | .17 |
| OFC | 68 | 5.5 | .05 |
| BATH | 53 | 5.5 | .05 |
| KIT | 138 | 11.2 | .08 |
| | 1227 | | .80 WEIGHTED |

AIR CHANGE
PER HOUR

+ 10 LR  OMIT
O 8 DR  $LN(73/31) = 1.12$
Δ 9 OFF $LN(78/34) = .83$

TIME, MINUTES

Figure 25

R. WRIGLEY RESIDENCE, RR.3, WARSAW
FRAME HOUSE OVER BASEMENT

1 B₁  LN(92/51) = .59
2 LR  LN(67/29) = .84
4 B3  LN(80/37) = .77
5 B4  LN(61/28) = .81

3 B₂  LN(97/42) = .84
6 BATH LN(81/31) = .96
7 KIT  LN(68/32) = .72

| SPACE | FT² | % TOTAL | |
|-------|-----|---------|-----|
| LR | 339 | 25.7 | .22 |
| KIT | 138 | 10.5 | .08 |
| B₁ | 123 | 9.3 | .06 |
| B₂ | 91 | 6.9 | .06 |
| B₃ | 145 | 11.0 | .09 |
| B4 | 169 | 12.8 | .10 |
| DR | 192 | 14.6 | .09 |
| OFF | 68 | 5.2 | .05 |
| BATH | 53 | 4.0 | .04 |
| | 1318 | | .79 WEIGHTED |

AIR CHANGE PER HOUR

10 LR OMIT
8 DR  LN(83/47) = .57
9 OFF LN(68/26) = .96

TIME, MINUTES

0    10    20    30    40    50    60

Figure 26

R.WRIGLEY RESIDENCE, RR. 3, WARSAW
FRAME HOUSE OVER BASEMENT

TEST NO 17
DEC. 8, 1960

① 1 B₁ LN(85/35) = .89
△ 2 DR LN(80/32) = .92
+ 3 B₂ LN(73/22) = 1.20
⊡ 4 B₃ LN(85/30) = 1.04

5 B4 LN(84/34) = .90
6 BATH LN(85/30) = .91
7 KIT LN(61/22) = 1.02

| SPACE | FT.² | % TOTAL | |
|-------|------|---------|------|
| LR | 339 | 27.1 | .27 |
| KIT | 138 | 11.0 | .11 |
| B₁ | 123 | 9.8 | .09 |
| B₂ | 91 | 7.3 | .09 |
| B₃ | 145 | 11.6 | .12 |
| B4 | 169 | 13.5 | .12 |
| DR | 192 | 15.4 | .12 |
| BATH | 53 | 4.2 | .04 |
| | 1250 | | .96 WEIGHTED AIR CHANGE PER HOUR |

8 DR LN(71/35) = .77
9 OFF OMIT
10 LR LN(84/34) = .90

TIME, MINUTES

Figure 27

# M. SPANN RESIDENCE



1 E      LN(90/70) = .25
2 LR     LN(79/52) = 1.52
3 B      LN(98/94) = .04
4 B₃     LN(90/70) = .25

5 B₂     LN(63/45) = .34
6 DEN    LN(77/51) = .41
7 BATH   LN(97/63) = .45
10 LR    LN(82/57) = .36

| SPACE | FT² | % TOTAL | |
|-------|-----|---------|------|
| LR   | 522  | 34.5 | .33 |
| KIT  | 174  | 11.5 | .05 |
| DEN  | 158  | 10.4 | .04 |
| B₁   | 204  | 13.5 | .03 |
| B₂   | 144  | 9.5  | .02 |
| B₃   | 126  | 8.3  | .02 |
| BATH | 96   | 6.3  | .03 |
| DR   | 89   | 5.9  | .03 |
|      | 1513 |      | .55 |

WEIGHTED AIR CHANGE
PER HOUR

8 DR    LN(79/52) = .42
9 KIT   LN(82/54) = .45

TIME MINUTES

Figure 28

# M. SPANN RESIDENCE

O 1 $B_1$    $LN(67/45) = .40$

△ 2 LR    $LN(60/38) = .46$

+ 3 $B_2$    $LN(70/46) = .42$

□ 4 $B_3$    $LN(69/55) = .24$

4

3

1

2

5 $B_2$    $LN(63/48) = .27$

6 DEN    $LN(67/35) = .49$

7 BATH    $LN(72/53) = .33$

5

7

6

| SPACE | $FT^2$ | % TOTAL | |
|-------|--------|---------|------|
| LR    | 522    | 34.5    | .12  |
| KIT   | 174    | 11.5    | .07  |
| DEN   | 158    | 10.4    | .05  |
| $B_1$ | 204    | 13.2    | .05  |
| $B_2$ | 144    | 9.5     | .03  |
| $B_3$ | 126    | 8.3     | .02  |
| BATH  | 46     | 3.0     | .02  |
| DR    | 89     | 5.9     | .03  |
|       | 1513   |         | .39  |

WEIGHTED AIR
CHANGE PER
HOUR

10

8

9

8 DR    $LN(67/40) = .52$

9 KIT    $LN(65/35) = .62$

10 LR    $LN(71/55) = .26$

10    20    30    40    50    60

TIME, MINUTES                    Figure 29

# M. SPANN RESIDENCE

1 $B_1$  LN(97/82) = .17
2 LR  LN(71/60) = .17
3 $B_2$  LN(88/73) = .19
4 $B_3$  LN(78/74) = .05

O 5 $B_2$  LN(61/48) = .23
△ 6 DEN  LN(66/46) = .36
+ 7 BATH  LN(81/68) = .18

| SPACE | FT.$^2$ | % TOTAL | |
|-------|------|---------|------|
| LR | 522 | 34.5 | .08 |
| KIT | 174 | 11.5 | .04 |
| DEN | 158 | 10.4 | .04 |
| $B_1$ | 204 | 13.5 | .02 |
| $B_2$ | 144 | 9.5 | .02 |
| $B_3$ | 126 | 8.3 | .00 |
| BATH | 96 | 6.3 | .01 |
| DR | 89 | 5.9 | .02 |
| | 1513 | | .23 |

WEIGHTED
AIR CHANGE
PER HOUR

8 DR  LN(70/54) = .26
9 KIT  LN(70/48) = .38
10 LR  LN(68/52) = .27

TIME, MINUTES

Figure 30

B. YEITER RESIDENCE

TEST
DEC

2 DR  LN (78/60)  OMIT
3 LR  LN (74/50) = .37
4 B₂  LN (96/62) = .44

1  B1  OMIT
5 KIT  LN (77/36) = .76
6 B₃  LN (94/64) = .38
7 BATH  LN (94/64) = .38

| SPACE | FT² | % | TOTAL |
|-------|-----|-----|------|
| LR | 320 | 33.7 | .22 |
| B₂ | 140 | 14.6 | .06 |
| B₃ | 140 | 14.6 | .06 |
| PUMP | 64 | 6.7 | .03 |
| KIT | 187 | 19.6 | .15 |
| LAUND | 60 | 6.3 | .05 |
| BATH | 43 | 4.5 | .02 |
|  | 954 |  | .59 |

WEIGHTED
AIR CHANGE PER
HOUR

8 PUMP  LN (98/64) = .43
9 LAUND  LN (78/37) = .75
10 LR  LN (72/28) = .94

TIME, MINUTES

Figure 31

(3,4)

1 B, OMIT

2 DR OMIT

3 LR  $LN(75/52) = .37$

4 $B_2$  $LN(75/52) = .37$

7

5   6

5 KIT  $LN(69/44) = .45$

6 $B_3$  $LN(73/44) = .50$

7 BATH  $LN(80/57) = .34$

| | AREA FT.$^2$ | % TOTAL | |
|---|---|---|---|
| LR | 320 | 33.7 | .14 |
| $B_2$ | 140 | 14.6 | .05 |
| $B_3$ | 140 | 14.6 | .07 |
| PUMP | 64 | 6.7 | .02 |
| KIT | 187 | 19.6 | .09 |
| LAUND | 60 | 6.3 | .03 |
| BATH | 43 | 4.5 | .02 |
| | 754 | | .42 |

WEIGHTED AIR CHANGE
PER HOUR

8

9

8 PUMP  $LN(102/74) = .32$

9 LAUND  $LN(86/51) = .52$

10 LR  $LN(72/46) = .45$

TIME  MINUTES

Figure 32

# W. DIECKMAN RESIDENCE

TEST NO. 23
DEC 15 1961

1 $B_1$ $LN(86/38) = .81$
2 $LR$ $LN(61/28) = .78$
3 $B_1$ $LN(73/30) = .89$
5 $KIT$ $LN(67/23) = 1.05$

4 $BATH$ $LN(76/42) = .60$
6 $B4$ $LN(100/52) = .65$

| SPACE | $FT^2$ | % TOTAL | |
|-------|--------|---------|------|
| $LR$  | 234    | 16.8    | .12  |
| $DR$  | 234    | 16.8    | .11  |
| $B_1$ | 198    | 14.2    | .12  |
| $B_2$ | 239    | 17.2    | .08  |
| $B_4$ | 223    | 16.1    | .10  |
| $KIT$ | 261    | 18.8    | .16  |
|       | 1389   |         | .59  |

WEIGHTED AIR
CHANGE PER HOUR

8 $B_2$ $LN(80/49) = .49$
9 $DR$ $LN(73/37) = .68$
10 $LR$ $LN(67/37) = .59$

TIME MINUTES

Figure 33

1 $B_1$  $LN(87/42) = .69$
2 $LR$  $LN(72/49) = .39$
3 $B_1$  $LN(77/30) = .94$
4 BATH  $LN(78/44) = .57$

5 KIT  $LN(67/32) = .75$
6 $A4$  $LN(100/50) = .69$
7 $B_2$  $LN(100/57) = .56$

| CHASE | FT² | % TOTAL | |
|---|---|---|---|
| LR | 234 | 13.8 | .07 |
| DR | 234 | 13.8 | .08 |
| $B_1$ | 198 | 11.8 | .10 |
| $B_2$ | 239 | 14.1 | .07 |
| $B_3$ | 245 | 14.4 | .08 |
| $B_4$ | 223 | 13.1 | .09 |
| KIT | 261 | 15.4 | .12 |
| BATH | 62 | 3.6 | .02 |
| | 1696 | | .63 |

WEIGHTED AIR
CHANGE PER
HOUR

8 $B_3$  $LN(54/50) = .47$
9 $DR$  $LN(74/42) = .57$
10 $LR$  $LN(74/42) = .57$

(7,10)

9
8
7
6
5
4
3
2
1

0    10    20    30    40    50    60

TIME, MINUTES

Figure 34

W. DIECKMAN

1 $B_1$ LN(97/84) = (.10)
2 LR LN(83/40) = .73
3 $B_1$ LN(85/43) = .69

4 BATH LN(87/52) = .52
5 KIT LN(68/30) = .82
6 $B_4$ LN(100/54) = .62
7 $B_3$ LN(115/83) = .33

| SPACE | FT² | % TOTAL | |
|---|---|---|---|
| LR | 234 | 13.8 | .13 |
| DR | 234 | 13.8 | .12 |
| $B_1$ | 178 | 11.7 | .08 |
| $B_2$ | 239 | 14.1 | .06 |
| $B_3$ | 245 | 14.4 | .05 |
| $B_4$ | 223 | 13.1 | .08 |
| KIT | 261 | 15.4 | .13 |
| BATH | 52 | 3.6 | .02 |
| | 1676 | | .67 WEIGHTED AIR CHANGE PER HOUR |

8 $B_2$ LN(74/47) = .45
9 DR LN(80/33) = .89
10 LR LN(77/25) = 1.13

TIME MINUTES

Figure 35

L. FARNSLEY R...

⊙ 1   US LN (72/44) = .49
△ 2   DR LN (67/41) = .49
+ 3   US LN (71/43) = .50
   4 BATH, OMIT

⊙ 5   LR LN (59/37) = .47
△ 6   B1 LN (68/41) = .48
+ 7 BATH, LN (54/27) = .70

| SPACE | FT.² | % TOTAL | |
|---|---|---|---|
| LR | 295 | 12.5 | .06 |
| KIT | 358 | 15.2 | .08 |
| US | 1221 | 51.6 | .25 |
| BATH, | 63 | 2.7 | .02 |
| B1 | 197 | 8.3 | .04 |
| B2 | 134 | 5.8 | .03 |
| OFF | 92 | 3.9 | .02 |
| | 2362 | | .50 WEIGHTED |

AIR CHANGE
PER HOUR

⊙ 8   B2 LN (60/38) = .46
△ 9   OFF LN (68/39) = .56
+ 10   KIT LN (68/39) = .56

10    20    30    40    50    60
TIME MINUTES

Figure 36

Figure 37

1 B OMIT

2 B LN(90/53) = .53

3 B LN(79/48) = .50

4 LR LN(80/45) = .57

5 LR LN(86/43) = .69

6 LR LN(88/51) = .56

7 BATH OMIT

8 DR LN(88/50) = .57

9 KIT LN(88/50) = .57

10 KIT OMIT

| SPACE | FT.$^2$ | % | Tₐ Tₕ |
|-------|---------|-----|-------|
| LR | 229 | 42.6 | .26 |
| B | 142 | 26.3 | .14 |
| KIT | 168 | 31.1 | .18 |
|  | 537 |  | .58 |

TIME, MINUTES

Figure 38

TEST No. 30
DEC. 21, 1960

1 BR OMIT
2 BR LN (19/19) = 1.00
3 BR LN (83/32) = .95

4 LR LN (89/49) = .59
5 LR LN (81/39) = .73
6 LR LN (84/42) = .69
7 BATH LN (85/47) = .59

| SPACE | FT² | % TOTAL | |
|---|---|---|---|
| LR | 229 | 39.9 | 27 |
| BR | 142 | 24.7 | 23 |
| KIT | 168 | 29.3 | 27 |
| BATH | 35 | 6.1 | 04 |
| | 574 | | BT WEIGHTED AIR CHANGE PER HOUR |

8 DR LN (86/47) = .60
9 KIT LN (81/31) = .96
10 KIT LN (74/23) = 1.17

TIME, MINUTES

# THE NATIONAL BUREAU OF STANDARDS

The scope of activities of the National Bureau of Standards at its major laboratories in Washington, D.C., and Boulder, Colorado, is suggested in the following listing of the divisions and sections engaged in technical work. In general, each section carries out specialized research, development, and engineering in the field indicated by its title. A brief description of the activities, and of the resultant publications, appears on the inside of the front cover.

## WASHINGTON, D.C.

**Electricity.** Resistance and Reactance. Electrochemistry. Electrical Instruments. Magnetic Measurements. Dielectrics.

**Metrology.** Photometry and Colorimetry. Refractometry. Photographic Research. Length. Engineering Metrology. Mass and Scale. Volumetry and Densimetry.

**Heat.** Temperature Physics. Heat Measurements. Cryogenic Physics. Equation of State. Statistical Physics.

**Radiation Physics.** X-ray. Radioactivity. Radiation Theory. High Energy Radiation. Radiological Equipment. Nucleonic Instrumentation. Neutron Physics.

**Analytical and Inorganic Chemistry.** Pure Substances. Spectrochemistry. Solution Chemistry. Analytical Chemistry. Inorganic Chemistry.

**Mechanics.** Sound. Pressure and Vacuum. Fluid Mechanics. Engineering Mechanics. Rheology. Combustion Controls.

**Organic and Fibrous Materials.** Rubber. Textiles. Paper. Leather. Testing and Specifications. Polymer Structure. Plastics. Dental Research.

**Metallurgy.** Thermal Metallurgy. Chemical Metallurgy. Mechanical Metallurgy. Corrosion. Metal Physics.

**Mineral Products.** Engineering Ceramics. Glass. Refractories. Enameled Metals. Crystal Growth. Physical Properties. Constitution and Microstructure.

**Building Research.** Structural Engineering. Fire Research. Mechanical Systems. Organic Building Materials. Codes and Safety Standards. Heat Transfer. Inorganic Building Materials.

**Applied Mathematics.** Numerical Analysis. Computation. Statistical Engineering. Mathematical Physics.

**Data Processing Systems.** Components and Techniques. Digital Circuitry. Digital Systems. Analog Systems. Applications Engineering.

**Atomic Physics.** Spectroscopy. Radiometry. Solid State Physics. Electron Physics. Atomic Physics.

**Instrumentation.** Engineering Electronics. Electron Devices. Electronic Instrumentation. Mechanical Instruments. Basic Instrumentation.

**Physical Chemistry.** Thermochemistry. Surface Chemistry. Organic Chemistry. Molecular Spectroscopy. Molecular Kinetics. Mass Spectrometry. Molecular Structure and Radiation Chemistry.

• Office of Weights and Measures.

## BOULDER, COLO.

**Cryogenic Engineering.** Cryogenic Equipment. Cryogenic Processes. Properties of Materials. Gas Liquefaction.

**Ionosphere Research and Propagation.** Low Frequency and Very Low Frequency Research. Ionosphere Research. Prediction Services. Sun-Earth Relationships. Field Engineering. Radio Warning Services.

**Radio Propagation Engineering.** Data Reduction Instrumentation. Radio Noise. Tropospheric Measurements. Tropospheric Analysis. Propagation-Terrain Effects. Radio-Meteorology. Lower Atmosphere Physics.

**Radio Standards.** High Frequency Electrical Standards. Radio Broadcast Service. Radio and Microwave Materials. Atomic Frequency and Time Interval Standards. Electronic Calibration Center. Millimeter-Wave Research. Microwave Circuit Standards.

**Radio Systems.** High Frequency and Very High Frequency Research. Modulation Research. Antenna Research. Navigation Systems. Space Telecommunications.

**Upper Atmosphere and Space Physics.** Upper Atmosphere and Plasma Physics. Ionosphere and Exosphere Scatter. Airglow and Aurora. Ionospheric Radio Astronomy.